Technical Bulletin

TB No: 036 | **Rev**: A | **Date**: May 12, 2006

Description: 9" Grabber Assembly Upgrade



Tesco Corporation 6204 – 6A Street SE Calgary, Alberta T2H 2B7 Phone: (403) 692 5700 www.tescocorp.com

A redesigned clamping box has been introduced for all models of Tesco Top Drives that use the 9" Grabber Assembly. The new clamping box is a one piece welded construction designed to prevent mechanical separation of the front and rear bolted plates from the assembly. In addition to improving safety by reducing the number of overhead parts (plates and bolts), this redesign will also reduce assembly and maintenance time.

AFFECTED PRODUCT:

BACKGROUND INFORMATION

Top Drive Models: HS, HC, HCI, HCI(S), EMI, EC, ECI and ECI(S) with 9" Grabber Assembly part number 8538.

ACTION RECOMMENDED:


Install new 9" Grabber clamping box part number 810065 (see item# 23 on attached illustration). With the exception of the Bolt Retaining Plate (part number 10194, not required), all remaining parts including the cylinder, die holders, hydraulic fittings, etc, can be reused to create the new 9" Grabber Assembly part number 720457.


REMINDER: Perform appropriate checks and inspections on parts selected to be reused.

Please contact Tesco Corporation at the following email address on issues specific to this bulletin.

Safety Technical Bulletins@TescoCorp.com

Contact your local Tesco Part Sales Center for supply of affected components as noted above.







	Grabb	er, 9'	1
Fie № I-720457-1.ai		Model ECI/HCI/EMI	
Dwg. No. 1-720457		Rev B	Sheet 1 of 1
050505	VNL	Checked	a APP E